Abstract estimate for constructing a circuit house for the use of His Highness the Maharaja of Mysore at Hassan.

No.	Items of work	Per	Ground floor Quantity	First floor Quantity
1	Earthwork excavating foundation and filling in basement	C. yd.	384	...
2	Concrete in mortar	C. ft.	3,358	...
3	Burnt brick in mortar foundation and basement	"	8 253	...
4	Burnt brick in mortar superstructure	"	9,672	8,540
5	Arch work brick in mortar	"	90	67
6	Burnt stone slabs 6" thick nicely dressed	S. ft.	1,159	503
7	Plastering with chunam	Sqr.	123·33	131·77
8	White and colour washing	"	123·33	131.77
9	Teakwood doors panel shutters complete	S. ft.	500	451
10	Teakwood windows with panel shutters outside and glazed shutters inside with iron bars etc., complete.	"	426	476
11	Pukka terrace roofing complete	Sqr.	35·50	4·32
12	Teakwood work heavy scantlings	C. ft.	289·60	...
13	Teakwood work wrought and put up	"	609·00	472·00
14	Roofing with 1st class Mangalore tiles over teak reepers, etc., complete	Sqr.	10·31	43,43
15	Ridge tiles set in mortar (ornamental)	R. ft.	85	296
16	Flooring with 9" square Mangalore tiles over 3" concrete bed and centre pointing.	Sqr.	19·78	30·78
17	Flooring with Cuddapah slabs over 3" concrete bed and cement pointing	"	8·40	...
18	Cornice 9" thick	R. ft.	275	73
19	Mortar beading	"	319	...
20	Teakwood trellis work as per plan	S. ft.	360	102
21	Do ornamental eave boards	R. ft.	286	546
22	Do planks 1½" thick with painting	S. ft.	84	84
23	Do ornamental railings with painting	R. ft.	75	80
24	Do finials (5 feet height)	Each	1	7
25	Silicate painting two coats	Sqr.	22·78	23·30
26	Fittings for doors	Each	15	17
27	Do for windows	"	21	24
28	Clearing site and levelling ground	Lump	sum Rs.	...
29	Sundry and unforseen items	Lump	sum Rs.	...
30	Teakwood brackets to support sun shades	Number	22	16
31	Bengal terrace roofing	Sqr.	...	1·43
32	Iron trusses	C.wt.	...	32
33	Ornamental parapet wall with top cornices	R. ft.	...	29
34	Teakwood planks ¼" thick with zinc sheets for valleys	S. ft.	...	282
35	Wood oiling and tarring to wood work	Sqr.	75·00	75·00
36	Teakwood main staircase complete	Lump	sum Rs.	...
37	Do servant staircase complete	Lump	sum Rs.	...
38	Sanitary fitting	Lump	sum Rs.	...
39	Water supply by means of pumping	Lump	sum Rs.	...

R. W. SCALDWELL,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is invited to pages 279 and 280 of the *Mysore Gazette* dated 4th April 1918 calling for tenders for constructing a Kitchen Block for the High School Students' Home at Chitaldrug. The last date for tendering is 15th April 1918.

N. ANANDALWAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

BANGALORE CITY MUNICIPALITY.

Abstract Notification, dated 22nd March 1918.

The attention of the public is invited to page 252, Part IV of the *Mysore Gazette*, dated 21st March 1918, calling for tenders for supplying brass badges required for the Public Conveyance Department. The last date for submitting the tender is 5th April 1918.

K. P. PUTTANNA CHETTY,
Honorary President.

BANGALORE CENTRAL JAIL.

Abstract Notification dated 22nd March 1918.

Notice is hereby given that sealed tenders will be received up to 9 A.M., on Tuesday the 18th June 1918, by the Superintendent, Central Jail, Bangalore, for the supply of articles required for petty constructions and repairs in the Bangalore Central Jail, for the year 1918-19.

Full details of supplies required and conditions for the tenders are published in the *Mysore Gazette*, dated 4th April 1918.